


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.  
Farm - M. Marchand "B" No. 2

SEC. 26 T. 20 R. 12W  
SW SW NW

Total Depth. 3378  
Comm. 4-24-49 Comp. 5-11-49  
Shot or Treated.  
Contractor. Stickle Drilling Co.  
Issued. 6-18-49

County. Barton  
KANSAS



CASING:  
10 3/4" 601' w. 400 sx. cem.  
7" 3366 w. 100 sx. cem.

Elevation. \_\_\_\_\_

Production. Pmp. 453.60 B.O.

Figures indicate Bottom of Formations.

|                |      |
|----------------|------|
| sand           | 155  |
| shale & sand   | 300  |
| red bed        | 591  |
| anhyd.         | 618  |
| shale & shells | 1310 |
| salt           | 1430 |
| shale & shells | 1580 |
| hrd. lime      | 1600 |
| shale & lime   | 1605 |
| brkn. lime     | 1845 |
| lime           | 1930 |
| shale          | 1960 |
| shale & lime   | 2541 |
| shale          | 2641 |
| shale & lime   | 2785 |
| lime           | 3080 |
| shale & lime   | 3103 |
| lime           | 3378 |
| Total Depth    | 3378 |
| R.T.D          | 3371 |

Tops:  
Stone Corral 591  
Topeka 2733  
Heebner 2996  
Brown Lansing 3120  
White Lansing 3137  
Arbuckle 3365

5-9-49 Drilled cement & shoes, hole filled up 150' in 1 hour.  
Drilled to 3374', hole filled up 1500' with oil in 8 hours.  
Swabbed hole down, and swabbed 79.30 barrels oil in 8 hours.

5-10-49 Acidized with 500 gallons acid through casing, no pressure, vacuum. Swabbed to bottom and tested for three hours, first hour, 12.71 barrels oil, no water; second hour, 7.06 barrels oil, no water; third hour, 9.88 barrels oil, no water.

5-11-49 Drilled deeper to 3378', hole filled up from 700' to 1200' while drilling, filled up to a total of 1500' of oil in 4 hours. Swabbed well to bottom and averaged 10 barrels oil per hour for 13 hours.

5-14-49 State test; pumped 453.60 barrels oil, no water, in 24 hours.