

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - THE TEXAS COMPANY
Farm - G. J. Soeken No. 1

SEC. 26 T. 20 R 12W
NE NE NE

Total Depth. 5380'
Comm. 12-15-49 Comp. 1-12-49
Shot or Treated. acidized
Contractor. Powell-Brunson Drilling
Issued. 2-12-49

County. Barton

KANSAS



CASING:
10 3/4" 595 w/300 sx cem
7" 3360 w/100 sx cem

Elevation. _____

Production. 138 bbl oil no wtr
Pumping

Figures indicate Bottom of Formations.

sand	200
sand, shale, shells	240
redbed	585
anhydrite	610
red bed	640
blue shale	850
shale, shells	1230
shale	1450
lime brkn	1740
lime	2135
lime brkn	2305
shale, lime brkn	2475
lime, shale	2550
shale	2600
lime	2665
lime, shale	2795
lime	2955
lime, shale	3009
lime	3125
lime, shale	3164
lime	3361
lime	3380
Total depth	

Tops:

Anhydrite	585
Br. Lansing	3109
Wh. Lansing	3125
Arbuckle	3358

1-8-49 Drilled cement, no show.
drilled to 3366--cleansed out
& tested for one hr, made 1 1/2
bailer oil--acidized w/500 gal
swabbed down recovered only acid
water

1-9-49 Drilled to 3380--acidized
w/1000 gal maximum pressure 1350 #
pumped in at 1000 # pressure drop
of 75 # in 5 min--swabbed down &
tested 1 bbl oil per hr w/ show of
water

1-10-49 Swabbed 3 bbl oil per hr
for 6 hr shut down for 8 hr
total fillup 290'

1-12-49 Ran tubing & acidized w/1500
gal, maximum pressure 1550 #
pressure drop of 150 # in 5 min.

1-14-49 Took completion test
pumped 138 bbl oil no wtr in
24 hr