

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas


Company - THE TEXAS CO.
Farm - G. J. Soeken No. 2

SEC. 26 T. 20 R. 12W
SW N E

Total Depth. 3369
Comm. 8-28-49 Comp. 9-13-49
Shot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 10-29-49

County. Barton

KANSAS



Elevation. _____

Production. Pmp. _____
Phys. 210 bbls.

CASING:

10 3/4" 590' cem w/206 sx. / 2942 sx.
7" 3349 cem. w/100 sx.

Figures Indicate Bottom of Formations.

sand	135
shale & shells	575
red bed	581
anhyd.	608
red bed	775
shale & shells	1240
salt	1400
shale & lime	1515
lime & shale	1655
lime	1915
lime & shale	2025
lime	2085
shale	2305
shale & shells	2515
lime & shale	2780
lime	2990
shale & lime	3110
lime	3369
Total Depth	

Tops:

Stone Corral	581
Hobbs	2975
Brown Lansing	3100
White Lansing	3115
Arbuckle	3347

9-11-49 Drilled cem. & drilled deeper to
3369' in lime. Hole filled up
2000' with oil in 4 1/2 hrs.

9-12-49 Swabbed 314 bbls oil in 24 hrs.

9-13-49 Acidized w/500 gals acid w/pilot
at 3358'. Max. press. 400# PSI
To vacuum. Fluid dropped to 1800'
after acid. Swabbed back 135
bbls of oil (128 bbl. load.)
Hole filled up 300' per hr with oil

Rotary Total Depth 3351'.