

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETRO. CORP.
Farm - Krone No. 1

SEC. 30 T. 20 R. 12W
SWc SW

Total Depth. 3531
Comm. 3-26-49 Comp. 5-16-49
Shot or Treated. Acid
Contractor. Mallard Drlg.
Issued. 7-23-49

County. Barton
KANSAS



CASING:
8 5/8" 295' cem. w/170 sx. cem.
5 1/2" 3491' cem. w/150 sx. cem.

Elevation. _____

Production. 30 BOPD trace wtr.

Figures indicate Bottom of Formations.

surface sand	190
red bed	710
anhyd.	740
shale & shells	1475
lime & shale	1640
lime	1995
lime & shale	2760
lime	3470
lime & shale	3490
Arbuckle	3496
dolo.	3531
Total Depth	

Tops:

Lime brn	3223
Lansing	3237
Congl.	3479
Arbuckle	3490

DSE 3241-48 op. 40", rec. 30' Rty. mud.
DST 3490-93 op. 30", rec. 7' mud.
DP & D.D. 4', SSO, 500 Acid, DD 3511,
500 Acid, took only 2 bbls. 1 GOPH, 3510-11,
DD 3521, 500 Acid, 50 qts. Bozooka shot,
no incr., DD 3522, no incr. 500 Acid, no help
DD 3527, 1 BOPH; DD 3531, 500 Acid, 60 GOPH
500 Acid, 150 GOPH, OB.

Measurements taken from derrick floor.