


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

Company- CHAS. HULME DRILLING
Farm- Tammen No. 1

SEC. 31 T. 20 R. 12W
NW NW NE

Total Depth. 3471'
Comm. 1-18-56 Comp. 2-7-56
Shot or Treated.
Contractor.
Issued. 6-2-56

County Barton
KANSAS



Elevation. 1858' RB

Production. 25 BOPD

CASING:

8 5/8" 270' cem w/300 sx
5 1/2" 3460' cem w/100 sx

Figures indicate Bottom of Formations.

sand	150
shale & shells	195
blue shale & shells	270
shale & shells	385
red bed	670
anhydrite	693
shale	1005
shale & shells	1530
lime	2200
shale & shells	2395
shale & lime	2915
lime	3165
shale	3205
lime	3462 RTD
lime	3471
Total Depth	

Tops:

Anhydrite	670
Heebner	3079
Brown Lime	3202
Lansing	3218
Shaley conglomerate	3443
Arbuckle	3459

DST #1 packer set at 3220', total depth 3280',
tool open 1 hr., good blow throughout test.
Rec. 240' of heavily oil and gas cut mud.
IFP 0#, FFP 100#, BHP 385# in 20 mins.

DST #2 packer set at 3360', total depth 3402',
tool open 1 hr., good blow throughout test.
Rec. 90' of heavily oil and gas cut mud.
IFP 0#, FFP 0#, BHP 825# in 20 mins.