


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- E. K. EDMISTON
Farm- DeWerff No. 1

SEC. 32 T. 20 R. 12W
NE NW NW

Total Depth. 3504'
Comm. 2-25-59 Comp. 3-7-59
Shot or Treated.
Contractor. Shelley-Miller Drlg.
Issued. 6-20-59

County Barton
KANSAS



CASING:

8 5/8" 264' cem w/175 sx.
5 1/2" 3499' cem w/50 sx.

Elevation. 1852' DF

Production. 119 BOPD

Meas. from top of RB. Figures Indicate Bottom of Formations.

sand	180
shale	340
red bed	656
Anhydrite	700
shale & shells	1550
lime & shale	2885
lime	3504 RTD
Total Depth	

TOPS:

Anhydrite (scout)	656
Heebner Shale	3069
Toronto Limestone	3085
Brown Limestone	3195
Lansing-Kansas City	3210
Base Kansas City	3438
Conglomerate	3443
Reworked Arbuckle	3458
Arbuckle	3488

DST 3420-3504' op 1 hr, good blow thruout
rec. 120' gas in pipe, 870' gassy muddy
oil, 210' oil, IBHP 1480#, IFP 240#,
FBHP 1010#, FFP 690#.