


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company - E. H. ADAIR OIL COMPANY
Farm - Lanterman No. 1

SEC. 34 T. 20 R. 12W
NW NW SE

Total Depth. 3396'
Comm. 10-16-48 Comp. 10-25-48
Shot or Treated.
Contractor. Company tools
Issued. 1-8-49

County. Barton
KANSAS



CASING:
Sur. Pipe, 250' cem w/110 sz.
5 1/2" 3395' cem.

Elevation. _____

Production. Est. 100 BO

Figures Indicate Bottom of Formations.

soil	10
sand	220
shale	945
shale, shells	1380
lime	1900
shale	2170
lime	2250
shale	2455
lime	2490
shale	2545
lime	2580
shale	2660
lime	3092
shale	3124
lime	3145
lime brown,	3160
limo, K.C.	3160
lime	3396
total depth	

Tops; D.F.

Hedner	3014
Brown Lime	3143
Lansing	3158
Arbuckle	3389
Rotary Total Depth	3394' D.F.

Circ. 1 hr 8 min @ 3245'.
Circ. 1 hr 42 min @ 3292'.
Circ. 1 hr 30 min @ 3333'.

It is recommended that pipe be set at 3392' Rotary table which is 3' off bottom.