

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company-KEWANEE OIL COMPANY

Farm- Lang

No. 6

SEC. 34 T. 20 R. 12W

CN/2 N/2 SE NE NE

745' frm NL, 330' frm EL, NE $\frac{1}{4}$

Total Depth. 3400 C.M.

PB 3399 C.M.

Comm. 2-21-52

Comp. 3-16-52

Shot or Treated.

Contractor.

Issued. 4-26-52

County

Barton

KANSAS



CASING:

8 5/8" 245.58' C.M. cem w/200 sx

5 1/2" 3383.68' C.M. cem w/100 sx

2 3/8" EUE tubing 3389.16' C.M.

Elevation. 1827 C.M.

Production. Pmp 71.58 bbls oil,
170 bbls water in 23 $\frac{1}{2}$ hrs.

Figures indicate Bottom of Formations.

surface	0
sand, clay	236
redrock	253
redrock, shale	553
anhydrite	605
shale, shells	1080
shale, shells, slate	1390
shab, shells	1440
shale, lime	1814
lime	1837
shale, lime	2862
lime	3035
shale, lime	3224
lime	3385
lime	3400

Total Depth C.M.

Plugged back to 3399 C.M.

Tops: Sample C.M

Anhydrite (driller's) 605

Heebner shale 3010

Brown Lime 3137

Lansing-Kansas City

lime 3156

Arbuckle dolomite 3282 $\frac{1}{2}$

Tops: Lane Wells C.M.

Heebner shale 3008

Brown Lime 3136

Lansing- K. C. lime 3151

Arbuckle dolomite 3383

Treatment Record:

Acidized w/1000 gal. Type "J" 15% on 3-10-52

Acidized w/2000 gal. Type "J" 15% on 3-12-52