

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - G. W. KEYES ETAL
Farm - Langrehr

No. 4

SEC. 34 T. 20 R. 12W
NE $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$

Total Depth. 3409

Comm. 10-27-49

Comp. 11-12-49


County. Barton

KANSAS

Shot or Treated.

Contractor.

Issued. 2-4-50



Elevation. _____

Production. Phy Pot 29 plus
65 wtr

CASING:
8 5/8 set at 263
5 1/2 set at 3399

Figures Indicate Bottom of Formations.

sand and shale	205
shale	225
red bed	263
shale shells and red bed	615
anhydrite	633
shale and shells	1100
salt and shale	1300
shale and shells	1485
shale and lime	1534
sdv lime	1590
lime and shale	1700
sand	1710
shale and shells	1740
sand lime and shells	1775
lime	1802
sand	1828
lime and shale	2185
shale and shells	2660
lime and shale	2760
lime	3024
shale	3028
lime and shale	3310
lime	3403
lime	3409
Total Depth	3409

Tops: Corrected 2' to derrick floor

Heebner	3022
Base Oread	3055
Br lime	3150
Lansing	3171
Arbuckle dolomite	3397

Total Rotary Depth: 3403 Moved in cable
tools, bailed hole, drilled cement and
cleaned out hole to total rotary depth.
Drilled deeper to Total Depth 3409'.