

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRLG. CO.
Farm- Batchman No. 2

SEC. 35 T. 20 R.12W
SE NW SE

County Barton

KANSAS



Total Depth. 3406
Comm. 10-13-53 Comp. 10-22-53

Shot or Treated.
Contractor. Birmingham-Bartlett
Date. 12-5-53

Elevation. 1835 R.B.

Production. Pmp. 50 BO & NW

CASING:
8 5/8" 249' cem. w/225 sx
5 1/2" OD 3402' cem. w/100 sx

Figures indicate Bottom of Formations.

sand	150
shale	250
redbed & shells	600
Anhydrite	620
shale & shells	1600
broken lime	2150
shale & shells	2835
lime & shale	2910
lime	2985
lime & shale	3126
shale	3146
lime	3406
Total depth	

Tops:	600
Anhydrite	3016
Heebner	3145
Brown lime	3159
Lansing	3399
Arbuckle	3406
RTD	

Remarks:
DST #1 3195-3231, open 40 min.
weak blow. Rec. 90' sl. gas cut
mud w/free spliks oil. BHP 420#
DST. #2 3239-50, open 15 min. rec.
25' mud. SO BHP 1150#
DST #3 3400-03, open 1 1/4 hrs. rec.
500' gas, 60' oil. BHP 840#
DST #4 3403-07, open 1 1/4 hrs. rec.
1320' gas, 120' oil. BHP 750#.
Drlg. in information:
Drilled plug. Bailed 1 1/2 BOPH
for 4 hrs.
Deepened 1 1/2', no increase
Acidized w/750 gal.
Swabbed 6 BOPH, 2400' off bottom.
POP.