


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRLG. CO.  
Farm- Patchman No. 6

SEC. 35 T. 20 R. 12W  
SE NE SE

Total Depth. 3398'  
Comm. 5-19-54 Comp. 5-28-54  
Shot or Treated.  
Contractor. Birmingham-Bartlett Drlg. Co.  
Issued. 6-1-57

County Barton  
KANSAS



CASING:  
8 5/8" 244' w/200 sx cem.  
5 1/2" 3397' w/125 sx cem.

Elevation. 1834 RB

Production. 3 1/2 BOPH for 6 hrs.

Figures indicate Bottom of Formations.

clay-sand	160
shale-red bed	245
red bed	601
Anhydrite	624
shale-shells	1400
lime-shale	1435
brkn lime	1575
lime-shale	1770
brkn lime	1930
lime-shale	2040
shale-shells	2070
s hale-lime	2240
shale-shells	2745
lime-shale	2830
lime	3035
shale	3143
brwn lime	3160
lime	3398
Total Depth	

TOPS:  
Anhydrite 601  
Heebner 3011  
Brown lime 3142  
Lansing 3154  
Arbuckle 3393

DST # 1 - 3370-97'. Open  
30 min. Weak blos. Rec. 8'  
mud. B HP 50#.

Acidized w/750 gal. Swabbed  
3 1/2 BOPH for 6 hrs. w/1350'  
fluid level & tr wtr.