


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRIG. CO.
Farm- Batchman No. 8

SEC. 35 T. 20 R. 12W
C N/2 NW SE

Total Depth. 3483
Comm. 4-25-55 Comp. 5-5-55
Shot or Treated.
Contractor, Birmingham-Bartlett
Issued. 6-11-55

County Barton KANSAS



CASING:

8 5/8" 250' cem. w/200 sx
5 1/2" 3483' cem. w/125 sx

Elevation. 1848 DF

Production. 30 bbls. oil per day

Figures indicate Bottom of Formations.

s and & clay	40
sand & shale	250
shale, shells, & redbed	618
Anhydrite	650
shale & shells	1425
shale & lime	2125
shale & shells	2700
lime & shale	2920
lime	3000
lime & shale	3165
lime	3413
coring Arbuckle	3483
Total depth	

Tops:	
Anhydrite	618
Heebner	3029
Brown lime	3158
Lansing	3171
Arbuckle	3407
RTD	3483

DST #1 3408-13, open 1 1/2 hrs. rec. 170'
gas & 670' free oil. BHP 1120#.
DST #2 3429-41, open 20 min.
slight blow, rec. 870' gas & 2080'
free oil and 100' wtr. BHP 1120#.
DST #3 3479-83. Open 30 min. rec.
450' water. BHP 1125#.
DST #4 3462-70. Open 20 min. Rec. 870'
water. BHP 1060.

Drig. in information:

Drilled plug and perforated 3426-30'
with 24 shots. Filled up with 350' oil first
hour. Put well on pump. Pumped up in 8
minutes. Completed as 30 BOPD.