


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINHAM-BARTLETT DRILLING CO.
Farm- Batchman "B" No. 1

SEC. 35 T. 20 R. 12W
SE SW NE

Total Depth. 3409
Comm. 11-18-55 Comp. 11-27-55
Shot or Treated.
Contractor. Birmingham-Bartlett Drilling Co.
Issued. 1-21-56

County Barton
KANSAS



CASING:
8 5/8 @ 239' w/ 200 sx cmt.
5 1/2 @ 3405' w/ 100 sx cmt.

Elevation. 1843 DF

Production. 30 BOPD

Figures Indicate Bottom of Formations.

sand, clay & shale	238
red bed, sand & shale	612
anhydrite	640
shale & shells	1440
shale & lime	2375
shale & shells	2560
shale & lime	2820
lime	2885
broken lime	2950
lime	3015
lime & shale	3230
lime	3412
correction	3409
Total Depth	

TOPS:

Anhydrite (driller)	612
Heebner	3027
Brown lime	3158
Lansing (corrected)	3169
Simpson (corrected)	3395
Arbuckle (corrected)	3402

DST #1: 3403-09, open 30 min. rec.
600' gas, 160' oil, BHP 800#

DP, FU 150'/30 min. 250'/2 hrs. 850'/
9 hrs. 1200'/12 hrs. 500 gal acid POP