


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRILLING CO. SEC. 35 T. 20 R. 12W
Farm- Lanterman No. 2 SE NE SW

Total Depth. 3429
Comm. 1-3-54 Comp. 1-12-54
Shot or Treated.
Contractor. Birmingham-Bartlett Drilling Co.
Issued. 3-13-54

County Barton
KANSAS



CASING:
8 5/8" 233' cem. w/210 sx
5 1/2" 3406' cem. w/ 125 sx

Elevation. 1844' RB

Production. 5 BO & 60 BWPD

Figures Indicate Bottom of Formations.

sand	0-200
red bed	253
red bed & shells	610
anhydrite	640
shale & shells	1425
broken lime	1870
shale & lime	2050
shale & shells	2525
lime & shale	2765
lime	3013
lime & shale	3165
lime	3405 RTD
lime	3429
Total Depth	

TOPS:
Anhydrite (drillers) 610
Heebner 3022
Brown Lime 3151
Lansing 3165
Simpson 3392
Arbuckle 3402

D.S.T. #1 3292-3302, open
45 min., rec. 10' mud,
No BHP

DRILLING-IN DATA:
1-14-54 - Moved in cable tools
Deepend to 3421', acidized
w/500 - but job no good.
1-16-54 - deepened to 3425',
Acidized w/750 gals.
1-17-54 - Deepened to 3429',
Swbd. 2 BO / wtr per hr.

Completed 1-18-54 & put on pmp.
2-26-54. Well now making 5 BO & 60 BWPD.