


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Komarek No. 1

SEC. 35 T. 20 R. 12W
SE NE NW
990' S, 330' W of N/4 corner

Total Depth. 3396
Comm. 8-5-49 Comp. 8-22-49
Shot or Treated. 500 gals. 8-23-49
Contractor. Transit Corp.
Issued. 1-28-50

County. Barton
KANSAS



CASING:

8 5/8" 235' cem w/200 sx.
5 1/2" 3305' cem w/125 sx.

Elevation. _____

Production. Phys. Pot. 78 oil,
trace wtr, 24 hrs.

Figures indicate Bottom of Formations.

sand, gravel	185
shale	220
red bed	630
anhydrite	645
shale, shells	1040
salt, shells	1170
shale, shells	1375
lime, shale	1555
lime brkn	1790
lime, sand	1820
lime	1825
lime, shale	2145
shale, shells	2285
lime	2475
shale, shells	2530
lime	2565
lime, shale	2710
lime	3090
shale, lime	3145
lime	3389
3389 RTD = 3386 SLM	
lime	3396
Total depth	

Tops: Corr.
Lansing 3146
Arbuckle 3384
Penetration 12'

Fillup:

1140' oil in 2 hrs, 10 mins at 3393
219' oil in 1 1/2 hrs at 3396
306' oil in 6 hrs, 40 mins.
491' oil in 12 hrs, 10 mins.
8-24-49, pumped 131 oil, 0.4% water
24 hrs.