


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Komarek No. 2

SEC. 35 T. 20 R. 12W
CN $\frac{1}{2}$ SE NW
990' N, 660' W of center

Total Depth. 3450 PB 3250
Comm. 6-3-50 Comp. 6-21-50
Shot or Treated. 500 gals 3193-3201
Contractor. Lohmann-Johnson
Issued. 9-23-50

County. Barton
KANSAS



Elevation. 1839

Production. dry

CASING:

8 5/8" 258' cem w/200 sx.
5 1/2" 3401' cem w/125 sx.
4 1/2" liner 3413' (29' of liner)

Figures indicate Bottom of Formations.

sand	224
red bed, shale	260
shale, red bed	890
shale, sand	1430
lime brkn	1658
shale, shells	1820
lime	1940
lime brkn	2385
lime, shale	2787
lime	3115
shale	3146
lime	3400
cong.	3402
lime	3407
3407 RTD = 3404 SLM	
lime, shale	3450
Total depth	

Tops: Corr.
Lansing 3159
Arbuckle (shaley) 3398
penetration 52'

slight show oil 3410-13
small show oil 3420-25
5 1/2 BW 1 hr, 50 mins @ 3450'
Set lane wells plug 3252; dumped
2 gals rock on plug PBTD 3250 SLM
Perf. 31 shots 3193-3201, no fluid.
Acid w/500 gals 3193-3201, did not
recover all of oil used in acidizing.
DST 3402-07, rec. 30' mud in 30 mins.