

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas


Company - THE TEXAS COMPANY
Farm - F. Komarek No. 1

SEC. 35 T. 20 R. 12W
SW SW NW

Total Depth. 3515 P. B. 3443
Comm. 9-21-49 Comp. 10-19-49
Shot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 12-17-49

County. Barton

KANSAS



Elevation. _____

Production. D & A

Figures indicate Bottom of Formations.

Sand	100
Shale & shells	150
Shale & sand	220
Red bed	612
Anhydrite	640
Shale & shells	1350
Salt	1400
Shale	1500
Lime	1990
Lime & shale	2120
Shale	2295
Shale & shells	2495
Lime & shale	2575
Lime	2700
Shale	2765
Lime	2810
Topeka lime	2863
Lime	3393
Conglomerate	3428
Lime	3515

Total Depth 3515 P.B. 3443

FORMATION TOPS

Stone Corral	612
Topeka	2754
Heebner	3037
Br. Lans.	3164
Wh. Lans.	3182
Simp.	3419
Arbuckle	3437

DST packer @ 3431-39, op. 1 hr. rec. 270' mud. Reset @ 3424-39, op. $1\frac{1}{2}$ hrs.
rec. 30' drlg. mud, BHP 0

S. O. 3456-57, Acid, 500 gals. $1\frac{1}{2}$ blr. WPH w/tr. oil

" 500 " $\frac{1}{2}$ & C.O. to btm. $1\frac{1}{2}$ blr wtr. w/ S.S.O. per hr.

" 1000 " @ 3472 no incr. oil or wtr.

" 2000 " @ 3460 shut down 40 hrs., bld. 30 GO bal fluid wtr.

Perf. 3431-41, acid 200 gals. $\frac{1}{2}$ & tested 15 GW w/ Sli. S.O. per hr.