


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas

Company- B IRMINGHAM-BARTLETT DRILLING  
 Farm- Alexian No. 2

SEC. 36 T. 20 R. 12W  
 NW SE SE

Total Depth. 3396'  
 Comm. 10-6-54 Comp. 10-14-54  
 Shot or Treated.  
 Contractor. Brimingham-Bartlett Drlg. Co.  
 Issued. 12-4-54

County Barton  
 KANSAS



Elevation. 1820' RB

Production Pmp. 30 BO/NW

CASING:

8 5/8" 250' w/200 sx cem.  
 5 1/2" 3389' w/125 sx cem.

Figures Indicate Bottom of Formations.

sand	150
shale-shells	259
red bed-shalle	578
Anhydrite	615
s hale-shells	1425
Broken lime	1505
shale-lime	1700
Brkn lime	1895
shale-lime	2265
shale-shells	2495
shale-lime	2810
lime	2871
shale-lime	3145
lime	3355
shale-Arbuckle	3392 RTD
shale-Arbuckle	3396

TOPS:

Anhydrite	578
Heebner	3005
B. Lime	3136
Lansing	3149
Simpson Shale	3381
Arbuckle	3386

Drilled pipe & deepened 4'  
 to 3396'. Filled up w/190'  
 oil. Acidized w/750 gals. &  
 put on pump to test. Pumped  
 1.6 NOPH for 14 hrs. Com-  
 pleted for 30 BOPD.