

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company. BIRMINGHAM-BARTLETT DRILLING CO.  
Farm. Alexian No. 5

SEC. 36 T. 20 R. 12W  
C W/2 SW SE

Total Depth. 3417

Comm 9-11-55

Comp. 9-18-55


County Barton

KANSAS

Shot or Treated.

Contractor. Birmingham-Bartlett Drilling Co.

Issued. 12-3-55



CASING:

8 5/8 @ 257' w/ 175 sx cmt.  
5 1/2 @ 3403' w/ 100 sx cmt.

Elevation. 1833 DF

Production. 30 BOPD

Figures indicate Bottom of Formations

sand & clay	257
sand, red bed & shale	550
red bed & shale	593
anhydrite	625
shale & red bed	1275
shale & shells	1517
broken lime	1548
shale & lime	1970
shale & shells	1995
lime & shale	3058
shale	3150
lime & shale	3284
lime	3345
lime & shale	3392
conglomerate & lime RTD	3405
lime	3417
Total Depth	

TOPS:

Anhydrite	593
Heebner	3019
Brown lime	3150
Lansing	3162
Arbuckle	3400

DST #1: 3401-05, open 1 hr. slight  
blow, rec. 75' oil, BHP 790#.

drld. plug. made 5 gal OGMPH, DD 3409,  
made 2 BOPH-FU 450' while bailing,  
ran tbg, axidized w/ 750 gal w/ pilot,  
1500 additional gal. acid. DD 3417,  
500 gal gel acid.