

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company - B & R DRILLING, INC.
Farm - Dannebohm No. 1

SEC. 36 T. 20 R. 12W
NE NE SW

Total Depth. 3450

Comm. 5-9-48

Comp. 5-23-48


County. Barton

KANSAS

Shot or Treated.

Contractor.

Issued. 6-12-48



CASING:
8 5/8" 242' cem. 210 sx.

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

sand	20
clay	30
sand	40
sand & shale	230
red bed	242
red bed & shells	346
red rock	562
red bed & shells	595
anhydrite	625
shale & shells	995
shale, broken lime, shells	1115
shale & salt	1362
shale & lime shells	1398
anhydrite & shale	1450
anhydrite	1460
shale & lime	1745
lime	1785
sandy lime & shale	1810
shale & lime	1875
lime	1950
lime & shale	2005
broken lime & shale	2105
lime & shale	2330
broken lime & shale	2440
lime & shale	2725
shale & sandy	2772
lime	2850
lime & shale	3175
lime	3205
lime & shale	3380
conglomerate	3390
lime & shale	3400
shale	3413
Arbuckle lime	3425
lime	3450
Total Depth.	

TOPS:

Top Brown lime	3149
Top Lansing K.C.	3164
Top Simpson Shale	3399
Top Arbuckle chert	3413
Top Arbuckle dolomite	3420