

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BIRMINGHAM-BARTLETT DRILLING CO.
Farm. Panning No. 3

SEC. 36 T. 20 R. 12W
SW SW NW

Total Depth. 3407

Comm. 5-15-55

Comp. 5-23-55


County Barton

KANSAS

Shot or Treated.

Contractor. Birmingham-Bartlett Drilling Co.

Issued. 7-30-55



CASING:
8 5/8 @ 235' w/ 200 sx cmt.
5 1/2 @ 3403' w/ 100 sx cmt.

Elevation. 1824 DF

Production. 20 BOPD

Figures indicate Bottom of Formations.

sand & clay	160
shale & shells	235
red bed & shells	500
red bed	595
anhydrite	620
shale & shells	1410
lime & shale	2785
lime	2875
lime & shale	2985
lime	3090
lime & shale	3143
lime	3407
Total Depth	

TOPS: (RBM)

Anhydrite	595
Heebner	3013
Brown lime	3142
Lansing	3154
Arbuckle	3396

Drld. plug & CO. Acid w/ 500 gal.
After load rec. hole tstd approx.
1 1/2 BOPH. 600' oil run in hole & Perf.
w/ 40 shots- no chnge in prod. so
acid, w/ 1000 gal. then hole tested
approx. 1 1/2 BOPH. POP.