


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETRO. CORP.
Farm - Schartz No. 1

SEC. 7 T. 20 R. 12W
S4 0 0 SE

Total Depth. 3426' D.F. P.B. 3280'
Comm. 11-21-48 Comp. 1-7-49
Shot or Treated. Acidized
Contractor. L-S-T Drilg. Co., Inc.
Issued. 1-2-49

County. Barton
KANSAS



CASING:
5/8" OD 361'
5-1/2" OD 3424'

Elevation. _____

Production. 302 Bbls.

Figures Indicate Bottom of Formations.

sand	75
shale	110
sand, iron & shale	140
sand & iron	157
shale	235
shale & sand	325
sand & red bed	362
red bed	600
anhydrite	680
shale & shells	950
salt	1250
shale & shells	1510
lime & shale	2000
shale & shells	2460
lime & shale	2555
lime	2630
lime & shale	2720
lime	2860
lime & shale	2935
brn lime & hrd lime	3005
lime	3050
lime & shale	3160
lime	3203
lime & brkn lime	3235
lime	3426
Total Depth - D.F.	

Tops: D.F.
Dawn Lime 3158
Lansing 3172
Arbuckle 3423

3174-75 small show oil sli. odor
D.S.T. 3195-3201, open 20, red.
35' oil & gas cut mud.
DET 3210-32 open 30, good blow
gas, rec. 165' oil & heavy
oil cut mud.

lane well plug 3280', Perf. 24
shots 3230-34, 20 gals. oil per
hr. 1000 acid. 5 BOPH, no wtr.
24 hr prep. test 118 BO, no wtr.
plug back T.D. 3280'