


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ALPINE OIL & ROYALTY CO.
Farm- Lizzie Buckbee No. 5

SEC. 14 T. 20 R. 12W
NW NE SW

Total Depth. 3401'
Comm. 3-2-59 Comp. 3-9-59
Shot or Treated.
Contractor. Quaker Drig. Co.
Issued. 4-25-59

County Barton
KANSAS



Elevation. 1807' KB

CASING:
8 5/8" 200' cem w/200 sx.
5 1/2" 3373' cem w/125 sx.

Production. 25 BOPD

Figures Indicate Bottom of Formations.

sand & gravel	110
blue shale	200
red bed	580
Anhydrite	606
shale	1100
shale & shells	1450
sand	1520
lime & shale	2000
shale	2590
lime & shale	3015
shale	3122
lime & shale	3265
lime	3375 RTD
lime	3401
Total Depth	

TOPS:	
Heebner	2995
Brown Lime	3121
Lansing	3138
Base Kansas City	3364
Arbuckle	3371