


CROWN PETRO. CORP. ET AL  
 Anna Krueger No. 1.

SEC. 14 T. 20 R. 12W  
 CEL SE SE

Total Depth. 3364'  
 Comm. 3-6-40 Comp. 3-27-40  
 Shot or Treated.  
 Contractor. Comet Drlg. Co.  
 Issued. 5-11-40

County. Barton



Rotary

CASING:  
 10 " 286'  
 5 1/2 " 3347'

Elevation.

Production. Pot. 300 B.

Figures Indicate Bottom of Formations.

sand	140	show oil 3346-47
shale	286	8 Bailers live oil when
sand	364	plug was drilled out
shale	605	more oil 3356-59
anhydrite lime	674	hole filled 300' in 1 hr
lime	690	more oil 3359-61
shale & shells	1100	hole filled 400' in 2 hrs.
salt	1216	total fillup 2900' in 15 H.
shale & shells	1370	
lime	1386	
shale	1421	
lime	1490	
shale	1497	
lime	1545	
shale & shells	1835	
lime	1905	
shale	1915	
shale & shells	1935	
lime	1982	
shale & shells	2025	
lime	2040	
shale	2055	
lime	2080	
shale & shells	2130	
sand lime	2145	
lime	2195	
shale	2200	
lime brkn	2260	
shale	2280	
lime	2315	
shale	2420	
lime	2450	
shale	2480	
lime	2500	
shale	2505	
lime	2515	
shale	2535	
lime	2545	
shale	2562	
shale & shells	2671	
shale	2740	
lime	3015	
shale	3038	
red rock	3088	
shale	3094	
lime	3096	
shale	3102	
lime K.C.	3117	
shale	3122	
lime	3286	
shale & lime	3346	
shale green & lime	3356	
lime	3364	
Total Depth.		

Top Arbuckle lime 3346