

State Kansas County Rice

Company Okmar Oil Co. Well No. 11

Farm Hill

Survey

Block No. Sec. 12 Twp. 20 S Range 10 W

Co-Ord. Elev. 1772' K/B

Ctr. NE/4 NW/4 SW/4

Koenig					

DRY HOLE CONTRI. (\$2,000.)

75% - Don Ingling, et al

18.75% - M-R Oil Co.

6.25% - L. J. Plym

Arb. test unless comp. as
producer in Simpson

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
11/12/65		M.I.R.T.
	2286	Tarkio Sd. (-514)
	2434	White Cloud Sd. (-662)
	2566	Severy Sand (-794)
	2870	Toronto (-1098)
	2880	Douglas (-1108)
	3003	Lansing (-1231)
DST #1	3026-42'	- Op 40", wk. bl. 25",
		Rec. 10' mud, no shows,
		FSIP 41#, FP 0#

Date	Depth	
		694742
	3296	(2' lower than #1 Koenig) Conglomerate
DST #2	- 3294-3306'	- (packer stuck @ 3054'
		wk. bl for 5" & died, BHP 919-919#
		freed packer, conditioned hole
		to test
(re-run)	Op 30"	very str bl when trying to
		come out of hole, packer stuck on
		bottom, ran bucket on measuring
		line inside D.P. & found fluid
		(salt wtr.) 1420' from surface
		Dialog found sd in D.P. @ 2954' &
		on second shot the Dp unscrewed @
	2896'	
11/21		Using jars the DST tool threads in
		the middle pulled free & pulled
		balance of D.P. & upper half of tool
		found 420' of white sd. in bottom
		of D.P. , bottom half of tool & one
		pressure gauged still in hole,
		trying to jar free
11/24		Fish recovered, regu. drlg. resumed
	3320	Sp. Sd. (-1548) 26' lower than
	3341	R.T.D. #1 Koenig
	3322	Sp. Sh
DST #3	- 3320-24'	- Tool went to 3000'
		& stopped because of bridge in hole
		D & A 11/25/65