

19-20-13W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WESTERN PETROLEUM EXPLORATION CO.
Farm - Titus No. 1.

SEC. 19 T. 20 R. 13 W
N Eo NW

Total Depth. 3576'
Comm. 12-30-43 Comp. 1-18-44
Shot or Treated.
Contractor. Mouser Drlg. Co.
Issued. 4-15-44

County. Barton
KANSAS



CASING:
8 1/4" 525'
5 1/2" 3538'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface & sand	100
sand & shale	253
sand	285
shale	363
sdv red rock	475
red rock	525
red bed	766
lime	797
shale & shells	1240
salt	1420
shale	1595
shale & lime	1635
lime	1645
lime & shale	1665
lime	1724
shale	1736
lime	1870
shale & lime	1920
lime	1934
chert	1968
lime	2015
lime & shale	2047
shale	2055
lime	2105
shale & lime	2116
lime cherty	2180
lime	2270
shale & lime	2288
lime	2345
shale	2402
shale & lime	2415
lime	2482
shale & lime	2670
lime	2716
shale & lime	2820
lime	2864
cherty lime	2878
lime	3131
shale & lime	3152
lime	3170
lime & shale	3201
shale	3225

~~Miss (Corr. 3522-3529)~~ 3400
conglomerate 3529
Arbuckle lime 3576
‡ NO & WPH,
Est. 200,000 ft. gas-abnd
Total Depth.

Tops: Topeka 2908
K. C. Lime 3251
Arbuckle (Corr.) 3528