


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
506 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.  
Farm- Titus "D" No. 1

SEC. 17 T. 20 R. 13W  
SE SE NW

Total Depth. 3540  
Comm. 5-7-52 Comp. 5-18-52  
Shot or Treated.  
Contractor. Garvey Drilling Co.  
Issued. 6-28-52

County Barton  
KANSAS



8 5/8" CASING:  
224' cem w/175 sx

Elevation. 1873

Production. dry

Figures Indicate Bottom of Formations.

shale, shells	300
red bed	342
red bed, shells	750
anhydrite	772
shale, shells	1600
lime, shale	2901
lime	2985
lime, shale	3053
lime	3102
lime, shale	3190
shale	3216
lime	3540
Total Depth	RTD

Tops:	
Heebner	3107
Brown Lime	3220
Lansing	3233
Arbuckle	3489

DST #1 3221-64, open 1 hr.,  
rec. 360' gas plus 50' very slightly  
oil cut mud. 200# BHP

DST #2 3314-3359, open 40 mins. rec.  
30' mud, 1200# BHP.

DST #3 3356-3406, open 1 hr., rec.  
55' oil cut mud, and 90' gas, 170#  
BHP.

DST #4 3494-3507, open 1 hr., rec.  
45' oil cut mud, 75# BHP.

DST #5 3497-3519, open 1 hr., rec.  
50' mud, 120# BHP

DST #6 3516-40, open 1 hr, rec. 610'  
salt water, 900# BHP.