


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PETROLEUM, INCORPORATED
Farm. Denbo No. 1

SEC. 26 T. 20 R. 13W
NE SW SW

Total Depth. 3600
Comm. 10-5-56 Comp. 10-15-56
Shot or Treated.
Contractor. Garvey Drlg Co.
Issued. 11-10-56

County Barton
KANSAS



CASING:

Elevation. 1874 DF

8 5/8" 210' cem w/200 sx.

Production. Dry

Figures Indicate Bottom of Formations.

clay, sand	120
sand hard	130
clay yellow	190
shale blue	305
red bed	735
anhydrite	755
shale	825
red bed, shale,	
shells	1495
lime, shale	2565
lime	2710
shale, lime	2940
lime	3018
lime, shale	3264
lime	3535
lime cherty	3556
lime	3600
Total Depth	

Tops:

Anhydrite	725-	755
Heebner		3130
Toronto		3154
Douglas (Scout)		3170
Brown Lime		3252
Lansing		3264
Congl. (Scout)		3510
Simpson (")		3536
Arbuckle (")		3550