


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DUKE DRILLING CO.
Farm- Whaley No. 1 (Twin)

SEC. 28 T. 20 R. 13W
SE SE NW

Total Depth. 3440'
Comm. 8-27-59 Comp. 9-7-59
Shot or Treated.
Contractor.
Issued. 3-26-60

County Barton
KANSAS



CASING:
8 5/8" 287' com. w/235 sx.
4" 3439' com. w/125 sx.

Elevation. 1885

Production. 30 BOPD

Figures indicate Bottom of Formations.

surface sand	93
hard sand	127
soft sand	137
hard sand	155
shale & sand	300
red bed	730
anhydrite	763
shale & shells	1575
shale & lime	1885
lime & shale	2220
lime & shale	2465
lime & shale	2775
lime & shale	3007
lime	3060
lime	3139
shale - Heebner	3143
lime	3150
shale	3159
lime - Toronto	3179
shale - Douglas	3254
lime - Iatan	3266
lime, shale- Lansing	3440RTD
Total Depth	

TOPS:	
Anhydrite	730
Heebner	3139
Toronto	3159
Douglas	3179
Iatan	3254
Lansing	3266