


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- SCHERMERHORN OIL CORPORATION
Farm- Morrison No. 1

SEC. 28 T. 20 R. 13W
SE NE NE

Total Depth. 3581
Comm. 10-22-52 Comp. 11-2-52
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 11-14-53

County Barton
KANSAS



CASING:

8 5/8" 221' cem. w/270 sx
5 1/2" 3533' cem. w/110 sx

Elevation. 1887

Production. 515 BO & NW

Figures Indicate Bottom of Formations.

sand	110
sand & shells	120
sand	158
sand & blue shale	189
blue shale	221
shale & shells	240
sand	270
shale & shells	295
redbed	730
Anhydrite	750
shale & shells	1630
lime & shale	2945
lime	3136
lime & shale	3245
lime	3250
shale	3258
lime	3471
lime cherty	3495
shale	3533
conglomerate	3556
lime	3581
Total depth Rotary	

Tops:

Heebner	3127
Brown lime	3245
Lansing	3258
Arbuckle	3556

DST #1 3399-3412, open 1 hr, rec.
1500' free oil, BHP 510#.
DST #2, 3414-3433, open 1 hr, rec.
1300' free oil, BHP 700#.