


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- ROCKET DRILLING CO., INC.
Farm- McDonald No. 1

SEC. 34 T. 20 R. 13W
SE SW NE

Total Depth. 3592
Comm. 10-4-54 Comp. 11-18-54
Shot or Treated.
Contractor. Rocket Drilling Co.
Issued. 8-6-55

County Barton
KANSAS



Elevation. 1880 RB

Production. 1P 50 BOPD fr L-KC

CASING:

8 5/8 252' w/ 200 sx cmt.
5 1/2 3549' w/ 125 sx cmt.

Figures indicate Bottom of Formations.

sand	180
clay	232
shale	718
shale, shells & salt	1400
salt & shale	1520
lime	1695
sand	1700
lime	1730
sand	1740
lime	1915
sand	1920
lime	2245
lime & shale	2985
lime	3045
lime & shale	3291
lime	3530
conglomerate	3547
Arbuckle	3592
Total Depth Cable	
R.T.D. 3551'	
TOPS:	
Heebner	3128
Brown lime	3248
Lansing	3262
Conglomerate	3493
Arbuckle	3547

Ran Lane-Wells log

DST #1: 3250-3340, open 1 hr. gas to surf. 48 min. rec. 480' fluid (30' GCM, w/ specks oil, 30' SOGCM, 230' OGCM, 190' HOGCM, FP 140-220#, BHP 700#

DST #2: 3379-3413, open 1 hr., rec. 30' mud, BHP 490#

DST #3: 3417-90, open 1 hr. rec. 30' mud w/ SO in tool, BHP 170#

DP; CO to 3551, NS, DD 3564, SSO, 500 GA, no help, DD 3592, no inc. perf. 3529-33, NS, PB 3363 & perf 3337-40, NS, perf. 3316-29, 20 gal oil in 1 hr, tr. wtr. 1000 GA dn. pipe, swb. 4 1/2 to 5 BOPH, sh. wtr., swb. 3 BFPH, 30% wtr. perf. 3302-05, 3290-98, 3278-86, 3266-74, ran tbg. & acidized w/ 2000 GA in perf 3266-3305