


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.  
Farm- Janne No. 1

SEC. 23 T. 20 R. 14W  
SW NW SW

Total Depth. 3558  
Comm. 10-21-52 Comp. 10-31-52  
Shot or Treated.  
Contractor. Garvey Drilling Co.  
Issued. 2-7-53

County Barton  
KANSAS



CASING:

8 5/8 486' w/ 275 sx cement  
5 1/2 3455.5' w/ 100 sx cement

Elevation. 1894

Production. 23 BOPD, 1% water

Figures Indicate Bottom of Formations.

clay & sand	40
sand	160
shale	260
sand	347
red bed	818
anhydrite	836
shale & shells	1595
lime & shale	1790
lime	2105
lime & shale	3033
lime	3181
lime & shale	3303
lime	3530
conglomerate	3542
lime	3558
Total Depth	

TOPS:

Heebner	3163
Brown lime	3267
Lansing	3279
Arbuckle	3542

DST #1: 3282-3352 open 1 hr. rec 90'  
GC mud 60' OC mud 90' very hvy. OC  
mud 360' froggy oil BHP 760#

DST #2: 3394-3447 open 1 hr. rec 310'  
muddy salt water BHP 1170#

3547. RTD