


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.
Farm - Davis "C" No. 1

SEC. 25 T. 20 R. 14 W
SEc SW

Total Depth. 3543' DF
Comm. 10-2-46 Comp. 10-29-46
Shot or Treated. Acidized 1000 gals.
Contractor.
Issued. 11-16-46

County. Barton
KANSAS



Rotary 0-3530'
Cable 3530-3543'

CASING:

8 5/8" 614' Cem.
5 1/2" 3527' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale & sand	0-125
shale & shells	195
shale & sand	300
red rock	370
sand	550
shale & shells	614
red rock	660
shale & red rock	1150
shale & shells	1250
shale & salt	1543
shale & shells	1668
lime & shale	1760
lime	1990
shale & lime	2035
lime	2120
shale	2255
shale & shells	2690
lime brkn	2825
shale & lime	2890
lime	3155
lime & shale	3250
lime	3490
shale	3505
lime	3532
lime	3545

3545=3543 DF

Total Depth 3543 DF

Tops:
Kansas City 3262
Conglomerate 3506
Simpson 3513
Arbuckle 3524

Acidized w/1000 gals.

At Q.D. 3543 in the Arb. had

3 BWPH after swbg. load out.

Set Lane-Wells plug @ 3340'. Btm
of plug @ 3344'. Perf. 36 holes
3277-88'; 22 holes 3310-16'.

Acidized w/1000 gal. Swbd. load
out, and then swbd for 9 hrs.

1 BWPH