


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BAY PETROLEUM CORP.
Farm - Weathers No. 2.

SEC. 26 T. 20 R. 14 W
NE NW SW

Total Depth. 3564
Comm. 5-3-46 Comp. 6-24-46
Shot or Treated.
Contractor.
Issued. 7-13-46

County. Barton
KANSAS



CASING:
8 5/8" 830'
5 1/2" 3536'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand 110
shale & shells 305
sand 330
shale & shells 402
sand & shale
strks 587
shale & sand 808
anhydrite 842
shale & shells 1355
salt & shale 1555
shale & lime 1620
lime & anhy-
drite 1682
anhydrite 1778
lime brkn &
shale 1805
lime 1820
lime cherty 1835
lime 1920
lime brkn 1993
lime cherty 2003
lime & shale 2059
lime brkn &
shale 2087
lime 2137
lime & shale 2216
lime brkn 2351
shale & lime 2918
shale 2958
lime 2980
lime & chert 3036
lime 3204
lime & shale 3259
lime 3539
dolomite 3564
Total Depth

P.B. 3553 20 qts N.G., no inc oil.
500 Acid 1 BO & 1 BW/hr. Bad
cement job, squeezed. Drilled
cement. Squeeze job no good.
Resqueezed. Test 5 GO & 5 GW/hr.
1000 Acid 2 BOPH 40% oil 60%
Wtr. 2000 Acid 1 1/2 BW & 1 1/2 BOPH
6-24-46 Test 1 3/4 BW & 1/2 BO/hr.

Tops:

Anhydrite 820
Brown Lansing 3271
White Lansing 3286
Arbuckle 3535

Tests:

RTD 3537, 5 1/2" 3536 -
DP & DD 3545 test
10 GOPH, 500 Acid -
Swb. 1 BOPH 1000 Acid
Swb. 2 BOPH.

D.D. 3553 oil decreased 15
GOPH. DD 3564 TD. No inc.
in oil 2 GWPH