


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORPORATION
Farm - Tilla Taylor No. 2

SEC. 26 T. 20 R. 14 W
SW SE SW
330' NSL 990' WLL SE²SW²

Total Depth. 3600'
Comm. 10-30-44 Comp. 11-19-44
Shot or Treated.
Contractor.
Issued. 2-3-45

County. Barton
KANSAS



CASING:

13 3/8"
8 5/8"
5 1/2"

239' Cem. LI
889' Cem. LI
3600' Cem. LI

Elevation. _____

Production. Pot. 1080 BO, no wtr.
DD Deptho.

Figures. Indicate Bottom of Formations.

sand	160	Perf. 5 1/2" csg 3545-55
shale	200	Acidized 11-19-44 w/
iron	205	1000 Gals. thru perf.
shale	220	3545-55
sand & shale	250	
shale	260	
shale & sand	370	
shale sand & shells	585	
shale & shells	930	
red bed, shale & lime		
shells	1465	
shale & shells	1655	
lime	1845	
lime & shale	2125	
lime	2200	
shale & shells	2220	
lime & shale	2460	
shale & lime shells	2535	
lime & shale	2680	
shale & lime	2700	
lime	2830	
lime, shale & sand	2935	
lime	3075	
lime & shale	3295	
lime	3340	
lime K. C.	3395	
lime & chert	3450	
lime	3525	
chert	3527	
arbuckle	3530	
lime & chert	3550	
lime	3600	
Total Depth.		

Tops:

Base Oread	3209
Brown Lime	3280
Lansing K. C.	3291
Marmaton	3514
PBC	3520
Arbuckle	3522