


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORP.
Farm - Tilla Taylor No. 3

SEC. 26 T. 20 R. 14 W
SWc SW

Total Depth. 3595 PB 3572
Comm. 11-28-44 Comp. 12-21-44
Shot or Treated. 2000 Gal Acid 12-21-44
Contractor.
Issued. 4-7-45

County. Barton
KANSAS



CASING:
13 3/8" 207' Cem LI
8 5/8" 850' Cem LI
5 1/2" 3594' Cem LI

Elevation. _____

Production. Pot. 1583 B Depth
Pumpd 347 B wtr

Figures Indicate Bottom of Formations.

surface clay	0-39
sand	120
shale	221
iron pyrite	225
shale	273
sand	281
shale	310
sand	325
shale & sand	500
red bed & shale	810
shale & shells	825
anhydrite	840
shale & shells	853
red bed & shale	985
shale & shells	1350
salt & shale	1420
shale & shells	1620
lime & shale	1735
lime	1820
iron pyrite & lime	1835
lime brkn	1920
lime	2025
lime brkn, & shale	2265
shale & shells	2740
lime	2800
shale & shells	2840
shale & lime	2990
lime	3170
shale & lime	3240
shale & shells	3253
K.C. lime	3300
lime	3530
Simpson shale	3535
Arbuckle lime	3545
lime	3595
Total Depth	

Tops:
Base Oread 3219
Lansing 3292
Base Kansas City 3505
Penn. Basal Congl 3520
Simpson 3523
Arbuckle 3535

Perforated 3535-3559