


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.
Farm - Price Bondurant No. 1.

SEC. 26 T. 20 R. 14 W
NE SW NE
1650'fEL 1650'fNL NE $\frac{1}{4}$

Total Depth. 3598 PB 3305
Comm. 3-8-45 Comp. 4-12-45
Shot or Treated.
Contractor. Kiowa Drlg. Co.
Issued. 6-2-45

County. Barton
KANSAS



Rotary O-3551
Cable 3551-3598

CASING:
8 5/8" 814' Cem.
5 1/2" 3541' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface & sand	170	Perf. 3297-3336 39 shots
shale	270	no show oil or wtr.
sand	520	Run Bridge Plug bottom 3322
shale	600	Run sand on top plug, plug
sand	610	back to 3305
red bed	804	Perf 3275-86 20 shots acidize
anhydrite	814	w/500 gals treating time
sand & shale	1020	1 hr 6 min. Swbd hole down
shale & shells	1350	showing 4 gals wtr & 1 qt OPH
shale	1385	
shale & salt	1610	
lime & shale	1710	
shale & sand	1785	
shale & shells	1885	
sand, lime & shale	1925	
lime & shale	2570	
lime	2575	
shale	2620	
lime & shale	2684	
lime brkn	2760	
lime	2845	
lime & shale	2906	
lime	3180	
lime & shale	3278	
lime	3412	
lime & shale	3472	
lime & conglomerate	3537	
Simpson Sand Core #1	3545	
Simpson Sand Core #2	3551	
lime	3598	

Total Depth

Plugged back 3305

Tops:

Topeka	2893
Lansing	3279
Base-K.C.	3506
Conglomerate	3530
Arbuckle	3550

From 3547-51 5 gal OPH
(Rotary TD 3551)

Run 500 Gals acid 3551
no results, Max pressure
1250# min. 650# treating
time 1 hr. 55 Min.

Core -- 3539-47 5' rec.
some sh Oil
3547-51 4' rec. good
sat. from 3548-3550

Cable tools from 3551-3598
13 BWPH Plugged back to 3550
Perf. from 3365-74 10 shots
3 BWPH
Set Lane Wells plug @ 3355