


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL COMPANY, INC. ET AL  
Farm- Russell No. 1

SEC. 27 T. 20 R. 11W  
SW SW SE

Total Depth. 3622  
Comm. 4-2-53 Comp. 4-11-53  
Shot or Treated.  
Contractor.  
Issued. 11-21-53

County Barton  
KANSAS



CASING:  
8 5/8" 576' cem. w/350 sx

Elevation. 1905 KB

Production. Dry

Figures indicate Bottom of Formations.

clay & sand	145
shale & shells	270
sand & iron	380
sand & shale	520
red bed	830
anhydrite	855
shale & red bed	1005
shale & shells	1650
shale & lime	2835
lime	3255
sand & shale	3315
lime	3622
Total Depth	

Tops:	
Heebner	3194
Brown Lime	3298
Lansing	3308
Conglomerate	3553
Arbuckle	3581

DST: #1 3222-3287' packer failed  
DST: #2 3217-3287 packer failed  
DST: #3 3302-3319 open  
30 mins. rec. 1100' salt  
wtr. BHP 1240#.  
DST: #4 3585-3622 open  
30 min. rec. 215' muddy  
salt wtr. BHP 1120#.