

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - CHAMPLIN REFG. CO.
Farm - Christianson No. 1.

SEC. 29 T. 20 R. 14 W
NE SW NE
1650'SNL & 1650'WEL NE $\frac{1}{4}$

DISCOVERY WELL

Total Depth. 3650
Comm. 3-18-45 Comp. 5-9-45
Shot or Treated.
Contractor.
Issued. 7-7-45

County. Barton
KANSAS



CASING:
12 $\frac{1}{2}$ " 80' 11" Cem.
5 $\frac{1}{2}$ " 3650' Cem.

Elevation. _____

Production. 6,000,000 G

Figures Indicate Bottom of Formations.

sand	0-28
clay	45
sand & shale	205
shale	290
sand	390
red bed shale	500
shale red	595
shale	850
anhydrite	880
shale, shells & red rock	1030
shale & shells	1250
shale salt	1540
salt & shale	1600
shale & shells	1740
lime sdy	1800
lime	1885
lime & shale	2050
lime	2060
lime, shells, shale	2150
lime	2205
shale & lime	2470
shale & shells	2615
lime brkn	2660
lime	2960
lime shale	3010
lime	3022
lime sdy	3030
lime	3145
lime & shale	3175
lime	3215
lime & shale	3300
lime	3365
lime hrd	3392
sft no odor	3395
lime	3550
conglomerate	3576
shale	3591
lime	3610
Arbuckle lime	3620
lime cherty strks	3645
lime	3650
Total Depth	

Tops:

Anhydrite	850
Topeka	2880
Lansing	3313
Simpson	3590
Arbuckle	3598