

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY THE PALMER OIL CORPORATION


SEC. 33 T. 20 R. 14W

FARM McGreevy "A" NO. 1

LOC. SE SE SW

TOTAL DEPTH 3553'
COMM. 4-25-51 COMP. 5-11-51
SHOT OR TREATED
CONTRACTOR The Palmer Oil Corporation
ISSUED 6-16-51

COUNTY Barton



CASING

8 5/8" 828' cem w/600 sxs.
5 1/2" 3547 1/2" cem w/90 sxs.

ELEVATION 1916 RB

PRODUCTION 3000 bbls.
Echo-Meter

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	223
shale	413
sand & shale	472
shale	643
shale & shells	826
anhydrite	857
shale & shells	1857
lime & shale	2145
shale & lime	2715
lime & shale	2916
lime	3174
lime & shale	3258
lime	3547
arbuckle lime	3548 RTD
arbuckle lime	3553
Total depth	

Tops: (R. B.)

Heebner	3168
Brown Lime	3270
Lansing	3281
Conglomerate	3536
Simpson	none
Arbuckle	3547

DST #1 3342-3368, tool open
15 minutes-recovered 320'
heavily oil & gas cut mud.
DST #2 3396-3444, tool open 17
minutes-recovered 2160' of oil, gas,
heavily oil & gas cut mud.
Acidized with 500 gallons on 5/13/51.
Acidized with 1500 gallons on
5/14/51. Acidized with 2000 gallons
on 5/16/51.