


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.  
Farm- Asher "B" No. 2

SEC. 34 T. 20 R. 14W  
NE SE SW  
990' N & 330' W of S/4c

Total Depth. 3552  
Comm. 6-27-54 Comp. 7-15-54  
Shot or Treated.  
Contractor. Barbour Drilling Co.  
Issued. 10-30-54

County Barton  
KANSAS



Elevation. 1912

8 5/8 @ 817' w/ 560 sx cmt.  
5 1/2 @ 3546' w/ 125 sx cmt.

Production. 237 BO, 4% water

Figures Indicate Bottom of Formations.

sand	275
sand & shale	335
sand, shale & red rock	650
red rock	810
anhydrite	830
shale & shells	1300
salt & shale	1495
shale & shells	1785
shale & lime	1930
broken lime	2210
broken lime & shale	2340
broken lime	2460
shale	2630
lime & shale	2850
lime	3035
broken lime	3105
lime	3173
shale	3176
lime & shale	3190
lime	3240
shale	3275
lime	3279
lime & shale	3285
lime	3500
lime & shale	3540
shale	3543
lime, SIM 3549 & 3546 RD	3552
Total Depth	
TOPS: (corrected)	
Heebner	3176
Brown lime	3278
Lansing	3289
Conglomerate	3522
Simpson shale	3530
Arbuckle	3546
Penetration	6

Fill Up:

65' oil in 1 1/2 hrs. @ 3550 1/2  
125' oil in 2 hrs @ 3550 1/2  
742' oil in 4 hrs, 10 min. @ 3552  
912' oil in 4 hrs. 40 min. @ 3552