

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Taylor "B" No. 3

SEC. 34 T. 20 R. 14W
C E/2 SE NE
660' N 330' W of E/4

Total Depth. 3535'

Comm. 4-5-48

Comp. 4-18-48


Shot or Treated.

Contractor. R.W. Rine Drilling Co.

Issued. 6-12-48

County. Barton

KANSAS



CASING:

8 5/8" 902' cem. 300 sx.
5 1/2" 3533' cem. 150 sx.

Elevation. _____

Production. 1190 oil, 227 vtr
Echo. Pot. 2 1/4 hrs.

Figures Indicate Bottom of Formations.

sand	105
sand & gravel	175
red rock & shale	505
red shale	820
gypsum & shells	902
shale & shells	1380
salt & shale	1560
shale & shells	1975
lime	2120
lime & shale	2415
shale & shells	2620
shale	2705
shale & lime	2800
lime & shale	2860
shale & shells	2905
lime & shale	3072
lime	3157
lime & shale	3286
lime	3405
lime & shale	3454
shale	3500
lime	3503
shale	3507
lime	3538

3538 Rot.TD-3535SLM.

TOPS:

Corr. Top Lansing	3266
Corr. Top Eros. Simpson	3508
Corr. Top Simpson	3518
Corr. Top Arbuckle	3532
Penetration	3

Fillup:

1400' oil in 35 min.
2180' oil in 1 hr 35 min.
2695' oil in 2 hrs 35 mins.
3000' oil in 5 1/2 hrs.