


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.
Farm - L. Pritchard No. 1

SEC. 34 T. 20 R. 14 W
NE 34

Total Depth. 3545'
Comm. 4-8-44 Comp. 5-26-44
Shot or Treated. 1000 Gals. Acid
Contractor. Mercury Drlg. Co.
Issued. 6-24-44 Rotary O-3542
Cable 3542-45

County. Barton KANSAS



CASING:

13 3/8"
5 1/2"

183' Cem.
3542' Cem.

Elevation. _____

Production. Pot. 1526 oil, no wtr.
Echometer

Figures indicate Bottom of Formations.

top soil & clay	15
sand & gravel	210
sand	350
shale	390
sand	410
red bed	650
red bed & shale	720
shale & shells	775
red bed	820
gyp	850
red rock	920
shale blue	945
shale & shells	1360
salt & shale	1457
salt	1575
shale blue	1610
lime	1835
shale & shells	1900
lime	1940
shale & shells	1980
lime	2022
shale	2028
lime	2196
lime brkn	2212
lime & shale	2376
lime	2446
lime & shale	2580
lime	2644
lime & shale	2842
lime	2884
shale	2926
lime	3214
shale	3275
lime	3522
sand hd	3528
lime	3548
Corrected	3548=3545
Total Depth.	

Tops:

Topeka	2880
Lansing	3281
Simpson	3518
Arbuckle	3544

Cores:

3280-95 8'10" Rec. Sat. Lime
3313-18 3'10" Rec. Sat. Lime
3370-82 10' Rec. very porous & sat.
11' Break from 3368-79