


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

Company - TEXAS CO.  
Farm - A.Wright No.2.

SEC. 35 T. 20 R. 14 W  
NE NW NW

Total Depth. 3600'  
Comm. 9-1-44 Comp. 10-14-44  
Shot or Treated.  
Contractor. Kiowa Drig. Co.  
Issued. 11-25-44

County. Barton  
KANSAS



Rotary O-3600

CASING:  
8 5/8" 810' Cem.  
5 1/2" 3597' Cem.

Elevation \_\_\_\_\_

Production. Pot. 2425 B.Pmp

Figures Indicate Bottom of Formations.

surface clay & sand	45	Tops:	
sand	250	Anhydrite	834
red bed & shale	280	Lansing	3288
sand & shale	335	KC Base	3512
shale & red bed	350	Simpson	3526
red bed	391	Arbuckle	3547
sand	430		
red bed & shale	570		
red bed	700		
red rock & shells	790		
red rock & shale	829		
anhydrite & lime	835		
red bed & shale	1080		
shale & lime	1270		
shale & shells	1515		
shale & lime shells	1655		
lime & shale	1692		
lime brkn	1830		
shale & lime	1910		
lime brkn	2010		
lime	2085		
shale & lime	2155		
lime	2220		
lime & shale	2690		
shale	2736		
lime & shale	2855		
shale & lime shells	2910		
Topeka lime	2942		
Porous lime	2965		
shale & lime shells	3000		
lime & shale shells	3050		
lime	3220		
lime & shale	3258		
shale	3282		
K C lime	3320		
lime	3380		
shale & lime	3435		
shale	3444		
shale & lime	3485		
lime	3520		
congl	3534		
sand & shale	3536		
shale green	3539		
Arbuckle	3576		
lime & shale	3600		
Total Depth			

Perf 3535-41 w/7 shots  
Perf 3539-42 w/12 shots  
2800' oil in 2 hrs.