


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg. Wichita, Kansas

Company TEXAS COMPANY  
Farm A. Wright No. 4

SEC. 35 T. 20 R. 14W  
SW SW NW

Total Depth. 3536'  
Comm. ~~12-19-47~~ Comp. ~~1-29-48~~  
Shot or Treated.  
Contractor. Kiowa Drlg. Co.  
Issued. 2-13-48

County. Barton  
KANSAS



CASING:  
8 5/8" 825' cem w/425 sx  
5 1/2" 3531' cem w/150 sx

Elevation. \_\_\_\_\_

Production. Pmp. 329 BO 7% Wtr.

Figures Indicate Bottom of Formations.

surface clay & sand	180
sand	385
shale & shells	425
red shale & shells	570
shale & shells	650
red bed & shale	800
red bed	814
anhydrite	840
shale & red rock	1025
shale & shells	1610
salt & shale	1740
shale & lime	2410
shale & shells	2545
lime & shale	2685
shale & shells	2795
lime & shale	3305
lime	3536
Total Depth	3536'

TOPS:

Heebner	3152
Lansing	3274
Conglomerate	3504
Simpson	3512
Arbuckle	3530

- 1-5-48 Ran DST packer @ 3302', open 25 min  
95' Oil & Gas cut mud.
- 1-8-48 Ran Schlumberger
- 1-15-48 Bailing mud at 3000'
- 1-17-48 Drilled plug, filled up 150'. drlg.  
to 3536' filled up 2700' in 11 hrs.  
Swabbed 106 Bbls. in 4 hrs. Swab-  
bed to bottom filled up 800' in 11 Hrs.
- 1-18-48 swabbed 20 BPH for 5 hrs.

Rotary Tool from 0 to 3533'  
Cable tool from 3533-36'