

P.O. Box 169

Great 1. Kansas 67530

Lease <u>WRIGHT</u>	Well No. <u>1</u>	Date <u>2-28-75</u>
County <u>BARTON</u>	Sec. <u>28</u> Twp. <u>20S</u> Rng. <u>14W</u>	Elevation
Company <u>Glenn Rupe</u>		Test No. <u>1</u>
Contractor <u>Red Tiger</u>		Zone Tested <u>K.C.</u>
Charge To <u>Glenn Rupe</u>		
Approved By <u>M. S. Clem</u>		Tester <u>F. Bowman-014</u>

Recorder No. 2826 Clock Range 12 Recorder No. 1620 Clock Range 12Depth 3322 Depth 3325Initial Hydro Mud Press. 1713 P.S.I.

Initial Flow Press. _____ To _____ P.S.I. Initial Flow Period _____ Min.

Initial Shut-in Press. _____ P.S.I. Initial Shut-in _____ Min.

Final Flow Press. 48 To 48 P.S.I. Final Flow Period 30 Min.Final Shut-in Press. 48 P.S.I. Final Shut-in 30 Min.Final Hydro Mud Press. 1703 P.S.I.Temperature 100 Other Charges _____Mud Weight 98 Viscosity 41Fluid Loss 188Interval Tested 3298 To 3328 Total 280.00Top Packer Depth 3293 Surface Choke Size _____Bottom Packer Depth 3298 Bottom Choke Size 5/8Total Depth 3328 Main Hole Size 7 7/8Drill Pipe Size _____ Wt _____ Rubber Size 6 3/4

Drill Collar I.D. _____ Ft. Run _____

Blow Very Weak Dead in 20 minRecovery 5' mud. oil speck on top Tool.

DST #1 3298-3328 open 30 - 51 30

Remarks WK flow 20" 3/4 dia. Re. 5' oil 5 psi/mud

IP48 FP48 SIP48 T-100° #3402

Sun Oilwell Cementing, Inc. shall not be liable for damages of any kind to the property or the personnel of the one for whom a test is made or for any loss suffered or sustained, directly or indirectly, through the use of its equipment, or its statement or opinion concerning the result of any test. Tools lost or damaged in the hole shall be paid for at cost by the party for whom the test is made.

P.O. Box 169

Great

1, Kansas 67530

Lease <u>Wright</u>	Well No. <u>1</u>	Date <u>3-2-75</u>
County <u>BARTON</u>	Sec. <u>28</u> Twp. <u>20 S</u> Rng. <u>14 W</u>	Elevation
Company <u>Glen Rupe</u>		Test No. <u>2</u>
Contractor <u>Red Tiger</u>		Zone Tested <u>SIMPSON</u>
Charge To <u>Glen Rupe</u>		
Approved By <u>John G. Carl</u>		Tester <u>F. BOWMAN-014</u>

Recorder No. 1620 Clock Range 12 Recorder No. 2826 Clock Range 12Depth 3552 Depth 3555Initial Hydro Mud Press. 1932 P.S.I.Initial Flow Press. 48 To 126 P.S.I. Initial Flow Period 45 Min.Initial Shut-in Press. 361 P.S.I. Initial Shut-in 45 Min.Final Flow Press. 146 To 214 P.S.I. Final Flow Period 60 Min.Final Shut-in Press. 351 P.S.I. Final Shut-in 60 Min.Final Hydro Mud Press. 1842 P.S.I.Temperature 116Mud Weight 98 Viscosity 46Fluid Loss 120Interval Tested 3530 To 3558

Price Job <u>280.00</u>
Other Charges
Total <u>280.00</u>

Top Packer Depth 3525 Surface Choke SizeBottom Packer Depth 3530 Bottom Choke Size 5/8Total Depth 3558 Main Hole Size 7 7/8Drill Pipe Size Wt Rubber Size 6 3/4

Drill Collar I.D. Ft. Run

Blow Good Throat Test.Recovery 20' mud - 186' watery mud, 248' muddy waterRemarks No show of oil.

P.O. Box 169

Great

d, Kansas 67530

Lease <u>Wright</u>	Well No. <u>1</u>	Date <u>3-3-75</u>
County <u>BARTON</u> Sec. <u>28</u> Twp. <u>20 S</u> Rng. <u>14 W</u>	Elevation	
Company <u>Glen Rupe</u>	Test No. <u>3</u>	
Contractor <u>Red Tiger</u>	Zone Tested <u>ARTB.</u>	
Charge To <u>Glen Rupe</u>		
Approved By <u>[Signature]</u>	Tester <u>F. Bowman 014</u>	

Recorder No. 1620 Clock Range 12 Recorder No. 2826 Clock Range 12Depth 3626 Depth 3629Initial Hydro Mud Press. 1932 P.S.I.Initial Flow Press. 58 To 429 P.S.I. Initial Flow Period 30 Min.Initial Shut-in Press. 1149 P.S.I. Initial Shut-in 45 Min.Final Flow Press. 458 To 788 P.S.I. Final Flow Period 60 Min.Final Shut-in Press. 1139 P.S.I. Final Shut-in 60 Min.Final Hydro Mud Press. 1932 P.S.I.Temperature 120Mud Weight 78 Viscosity 46Fluid Loss 120Interval Tested 3617 To 3632

Price Job	<u>280.00</u>
Other Charges	
Total	<u>280.00</u>

Top Packer Depth 3612 Surface Choke SizeBottom Packer Depth 3617 Bottom Choke Size 5/8Total Depth 3632 Main Hole Size 7 7/8Drill Pipe Size Wt Rubber Size 6 3/4

Drill Collar I.D. Ft. Run

Blow STRONG THROUT TEST. Slid 4' To BottomRecovery 1260' SALT WATER.

Remarks

Sun Oilwell Cementing, Inc. shall not be liable for damages of any kind to the property or the personnel of the one for whom a test is made or for any loss suffered or sustained, directly or indirectly, through the use of its equipment, or its statement or opinion concerning the result of any test. Tools lost or damaged in the hole shall be paid for at cost by the party for whom the test is made.