


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - ALKAY OIL COMPANY
Farm - Schultz No. 1

SEC. 9 T. 20S R. 15W
NE SW SW

Total Depth. 3865'
Comm. 8-26-47 Comp. 9-10-47
Shot or Treated.
Contractor.
Issued. 10-11-47

County. Barton KANSAS



CASING:
10 3/4" 655' w/450 sx.

Elevation. _____

Production. Dry hole

Figures Indicate Bottom of Formations.

clay-	40
clay and sand	75
shale	175
sand	200
shale and shells	428
sand - soft	577
lime hard & sand	630
sand soft, pyritic	644
shale w/ strks. sand	750
red rock & shale	790
sand hard	800
red rock & shells	860
sand	870
shale and shells	975
lime and shale	1055
anhydrite	1080
shale and shells	1120
red rock and shale	1275
shale and shells	1525
salt	1625
salt and shale	1635
lime and shale	1705
shale and shells	1845
lime and shale	1925
lime	2080
lime and shale	2140
lime	2200
shale	2225
lime	2285
lime and shale	2380
lime broken	2405
shale	2475
lime	2505
lime and shale	2690
shale	2735
lime and shale	2765
shale	2795
lime and shale	2880
shale	2910
lime and shale	3115
lime	3170
lime broken	3190
lime and shale	3420
shale sticky	3451
lime	3487
lime soft	3491
lime hard	3551
lime very soft, oolitic	
porous. water	3586
lime	3598
lime moderately soft	3600
lime hard	3618
lime soft	3622
lime hard	3640
lime and shale	3653
lime soft, oolitic	
porous water	3661
lime and shale	3733

Conglomerate	3753
Cherty conglomerate	3753
cherty conglomerate	3865
Total Depth	3865

TOPS:	
Topeka	3115
Kansas City	3451
Conglomerate	3733