


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

HELMERICH & PAYNE, INC - W.C. JACKSON - F.L. FEASTER
Unruh No. 1.

SEC. 16 T. 20 R. 15W
CEL NE NW

Total Depth. 3872'
Comm. 6-18-41 Comp. 8-7-41
Shot or Treated.
Contractor.
Issued. 9-13-41

County. Barton



CASING:
8 5/8" 594' Cem.
5 1/2" 3724' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay, shale & sand	225
sand	260
shale & shells	400
sand	555
shale & red bed	655
shale red & shells	782
red bed & shale	1037
anhydrite	1060
red bed, shale & shells	1245
shale & shells	1695
shale strks lime	1790
lime brkn	1830
lime brkn & gyp	1930
lime	2070
shale-strks lime	2092
lime brkn	2195
lime	2225
shale & lime shells	2280
lime brkn	2605
lime & shale	2685
lime brkn	2775
shale	2800
shale & lime	2870
lime brkn	3020
lime	3060
lime brkn	3140
lime	3508
lime sft	3545
lime hrd	3557
lime	3710
conglomerate	3725
lime Arbuckle	3739
lime	3872

Total Depth.