


HELMERICH AND PAYNE, INC.
J.J. Schmidt No. 1.

SEC. 22 T. 20 R. 15W.
6Ea NW

DISCOVERY WELL

Total Depth 3763
Comm. 9-1-41 Comp. 9-26-41
Shot or Treated.
Contractor.
Issued. 11-1-41

County Barton.



CASING.

85/8" 690' cemented.
5 1/2" 3763 cemented.

Elevation.

Production. Pot. 14 BO,
1,587,000 Gas.

Figures Indicate Bottom of Formations.

surface clay shale & sholls	341
sand	450
shale and shells	485
shale	530
sand	542
shale and shells	690
shale	710
red bed and shells	776
red bed	943
anhydrite	963
sand and shale	1170
shale shells and salt	1685
shale and shells	1750
broken lime	1810
lime	2043
sdv lime	2060
lime	2683
shale	2733
lime	2795
broken lime	2900
lime and shale	3014
lime broken	3058
lime	3241
lime and shale	3358
K.C. lime	3386
lime	3500
lime and shale	3669
Arbuckle lime	3745
lime	3763
Total Depth.	