

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - MAGNOLIA PETROLEUM CO.  
Farm Matilda Radenberg No. 1


SEC. 24 T. 20S R 15W  
NW NE SE

Total Depth. 3640 KB  
Comm. 4/15/48  
Shot or Treated.  
Contractor.  
Issue. 7-3-48

Comp. 5/2/48

County. Barton

KANSAS



Elevation. \_\_\_\_\_

CASING: 8 5/8" @ 390' & cem.w/450 sacks  
5 1/2" @ 3636' & cem.w/200 sacks

Production. Flowed 1238 bbls oil,  
no water, 24hrs.

Figures Indicate Bottom of Formations.

surface clay	25
sand	150
shale & shells	314
sand	405
red bed	425
red bed & shale	585
shale & shells	875
anhydrite	890
anhydrite	912
shale & shells	1220
salt	1285
shale & shells	1925
lime	2120
lime & shale	2170
lime	2215
broken lime	2290
lime & shale	2490
shale & lime	2740
broken lime	2795
lime & shale	2950
lime	2960
broken lime	3035
lime	3275
shale & lime	3317
lime & shale	3428
lime	3458
lime & shale	3510
lime	3636
lime	3640 KB
Total Depth	3640 KB
Top Lansing	3315 K.B.
Top Arbuckle	3593 K.B. SLC